

P. O. DULIAJAN
DIST. DIBRUGARH
ASSAM, 786 602
TEL : (0374) 2800202, 2800221, 2800582
(0374) 2800556, 2800558
FAX : (0374) 2800557
e-mail : info@assamgas.org
Visit us : www.assamgas.org



CIN OF AGCL : U11101AS1962SGC001184

Ref: AGCL/TS/PNGRB/REPORT/15/2019/23

Date 17.04.2021

To,
The Secretary,
Petroleum Natural Gas Regulatory Board
1st floor , World Trade Centre
Babar Road, New Delhi - 110001

Sub: Submission of details as per Schedule I under regulation 4(2) of the PNGRB (Access Code Regulations- Declaration on capacity of the NG pipelines) regulations 2008 as on 01.04.2021.

Respected Madam,

With reference to the captioned subject, please find the Schedule I of Assam Natural Gas Pipeline Network(ANGPL) as on 01.04.2021 enclosed herewith as appendix I.

Thanking You,

Yours sincerely,

(G.K. Sarmah)
GM(I&TGG)

Encl : Schedule I as appendix I.

SCHEDULE – I

Data for Declaration of NG pipeline capacity
Month: April 2021

1. Name of entity : Assam Gas Company Limited, Duliajan

2. Name of pipeline : 20" NB / 23.11km Duliajan- Namrup Pipeline

3. Section wise capacity on the pipeline :

Provisional capacity 1.8 MMSCMD

(Actual capacity is being determined by CAG recommended by PNGRB)

(a) Number of sections: One(01) section

(b) Name of section with start and end point:

Start Point : AGCL compstation

& End Point : NTPS yard

(c) Capacity: (i) Volume terms : 1.8 MMSCMD (capacity of the entire NG network)
(ii) Energy terms : 71428 MMBTU

4. Number of AHAs : One(01)

5. Number of entry points on the pipeline route : One(01)

6. Location of entry points : AGCL compression station

7. Number of exit points : Two(02)

8. Location of exit points : 1. NTPS, Namrup, 2. APL, Namrup

9. Entry point wise capacity : 1.8 MMSCMD

10. Exit point wise capacity (to be furnished separately for each exit point):

1. NTPS, Namrup, Capacity: 0.88 MMSCMD

2. APL, Namrup, Capacity: 0.15 MMSCMD


11. Technical parameters:

(a) Inlet pressure at entry point : 18Kg/cm²

(b) Calorific value band at entry point : 8000 to 9000 KCal

(c) Temperature : 25 degree Celsius




G. K. SARMA
General Manager (I & TC)
Assam Gas Co. Ltd.
Duliajan

12. Status of extra capacity available in the pipeline system on common carrier basis: 0.77 MMSCMD

13. Details of common carrier capacity being used by transporter itself or on contract carrier basis: Utilized by transporter itself.

14. Any demand pending with the transporter for common carrier usage of the pipeline along with duration of such pendency: NIL

15. Preference on entry and exit points: NIL



A handwritten signature in blue ink, appearing to read "G. K. Sarma".


G. K. SARMA
General Manager (I & TGR)
Assam Gas Co. Ltd.
Duliajan

SCHEDULE - I

Data for Declaration of NG pipeline capacity
Month: April 2021

1. Name of entity : Assam Gas Company Limited
2. Name of pipeline : 14" NB & 16" NB / 24 & 56 Km Duliajan-Namrup- Lakwa Pipeline
3. Section wise capacity on the pipeline:
 - For Section 1 : 0.628 MMSCMD at 10.5kg/cm²
 - For Section 2 : 0.651 MMSCMD at 8.5kg/cm²
- (a) Number of sections:- Two(02) section
- (b) Name of section with start and endpoint:
 - i. Section 1: 14" NB / 24 Km
Start Point: AGCL Compressor station, Duliajan
End Point: NTPS, Namrup
 - ii. Section 2 : 16" NB / 56 Km
Start Point: NTPS, Namrup
End Point: Lakwa metering station
- (c) Capacity: (i) Volume terms : For Section 1: 0.628 MMSCMD & For Section 2: 0.651 MMSCMD
(ii) Energy terms: For Section 1: 24920 MMBTU & For Section 2: 25833 MMBTU
4. Number of AHAs: Two(02)
5. Number of entry points on the pipeline route: One(01)
6. Location of entry points: AGCL compression station
7. Number of exit points: Section 1: Nil & Section 2 : 20 Nos.
8. Location of exit points: As mentioned in SL10
9. Entry point wise capacity: For Section 1: 0.628 MMSCMD &
For Section 2: 0.651 MMSCMD




G. K. SARMA
General Manager (R & T)
Assam Gas Company Limited
Duliajan


10.Exit point wise capacity(to be furnished separately for each exitpoint):

Section-I :14" NB / 24 Km AGCL Compressor station, Duliajan: Nil

Section-II: NTPS, Namrup& 16" NB / 56 Km NTPS, Namrup to Lakwa metering station:

Names of exit (Tee Point)	Booked Capacity (MMSCMD)
1. Sola Forest	0.0022
2. Sufrai	0.0056
3. Barahi	0.0019
4. Hingorajan	0.0001
5. Bhojo	0.0031
6. Banfera	0.0078
7. Tingalibam	0.0012
8. Aideobari	0.002
9. Kanu	0.003
10. Bihubor	0.0045
11. Bihubor	0.0047
12. Salkathoni	0.0035
13. Baruakhat TP	0.0045
14. Bimalapur	0.0034
15. Shantipur	0.0048
16. Bhuyankhat	0.0032
17. Borhat	0.0021
18. TitlagarhChariali	0.0013
19. LTPS	0.5000
20. Jorhat Golaghat Gas Grid	0.0910
TOTAL	0.6499




G. K. SARMA
General Manager (I & TGG)
Assam Gas Co. Ltd.
Duliajan

11. Technical parameters:

(a) Inlet pressure at entry point: For section 1 : 10.5Kg/cm²

For section 2 : 8.5 kg/cm²

(b) Calorific value band at entry point : 8000 to 9000 Kcal (NetCV)

(c) Temperature : 25 degree Celsius

12. Status of extra capacity available in the pipeline system on common carrier

basis: For section 1 & section 2 : 0.6291MMSCMD

13. Details of common carrier capacity being used by transporter itself or on contract carrier basis: Utilized by transporter itself.

14. Any demand pending with the transporter for common carrier usage of the pipeline along with duration of such pendency: NIL

15. Preference on entry and exit points: NIL



A handwritten signature in blue ink, appearing to read "G. K. Sarma".

G. K. SARMA
General Manager (I & TGR)
Assam Gas Co. Ltd.
Duliajan