

P.O. DULIAJAN
 DIST. DIBRUGARH
 ASSAM, 786 602
 TEL : (0374) 2800202, 2800221, 2800582
 (0374) 2800556, 2800558
 FAX : (0374) 2800557
 e-mail : info@assamgas.org
 Visit us : www.assamgas.org



CIN OF AGCL : U11101AS1962SGC001184
 GSTIN : 18AABCA6977C1ZM

No:-Elect/145/RMCA/Pt-V/2021/07

Date:-07.05.2021

To

Type of Bid : **SHORT TENDER**
 Bidding type : **Single Bid**
 Bid closing on : **21/05/2021 at 10.00 hrs. (IST)**
 Bid Opening on : **21/05/2021 at 13.00 hrs. (IST)**
 EMD : **Rs. 2,300.00**

ASSAM GAS COMPANY LIMITED invites Sealed Tenders from the authorized dealers only for the items detailed below:-

SI No.	Item Description	Unit	Qty
01	Supply, installation & commissioning of 05 numbers of brand new 2 TON, 1.5 TON and 1 TON, 3 star split type Inverter Air Conditioners (Technical Specification as per Annexure) with 4 KVA and 5 KVA Voltage Stabilizers at AGCL Head Office , Duliajan	Job	01

Terms & Conditions for Limited Tender:

1. The bidder should quote their rates with applicable taxes etc. as per the FORMAT given below in official letter head of the company/firm etc.:

SI No.	Material Description	Unit	Rate/Unit (INR) (A)	GST @% (INR) (B)	Amount/ Unit INR (C)=(A)+(B)	Quantity (E)	Total Amount (INR) (F)= (D) × (E)
1.	Supply, installation & commissioning of 2.0 TON 3 star split type inverter Air Conditioners as per specification given in	Nos				02	

Annexure -I							
2	Supply, installation & commissioning of 1.5 TON 3 star split type inverter Air Conditioners as per specification given in Annexure -II	Nos				02	
3	Supply, installation & commissioning of 1.0 TON 3 star split type inverter Air Conditioners as per specification given in Annexure -III	Nos				01	
4	Supply, installation & commissioning of 5 KVA Voltage Stabilizer as per specification given in Annexure-I	Nos				02	
5	Supply, installation & commissioning of 4 KVA Voltage Stabilizer as per specification given in Annexure-II	Nos				03	
6	Supply & installation of AC brackets for installing the outdoor units of ACs	No				05	

Total (In figure):
Rupees (In words):

Note:

1. The bidder must submit the technical brochures of the items to be supplied mentioning the make and models of the AC and stabilizers.



2. The bidder should quote with maximum discount on quoted price. **The rates quoted should include transportation and handling charge of the items at site as mentioned above.**
 3. The TOTAL AMOUNT shall be in figure as well as in words. No overwriting shall be allowed. In case of discrepancy, the rates quoted in words shall be considered to be correct.
 4. Sealed envelope containing the bid duly filled in as per above Format on bidders letter head should reach Manager (Elect), Department of Electrical, Assam Gas Company Limited, Duliajan-786602, Dist-Dibrugarh (Assam) on or before the bid closing date and time mentioned above. If the bid closing date happens to be holiday/bandh call then the next working day will be considered as bid closing date. In case next working day is Saturday, the bid closing date shall be Monday.
 5. The Sealed envelope containing the bid shall be marked at the top of the envelope with following details:-
 - a) AGCL Tender No.
 - b) Bid Closing date
 - c) Bidder's Name
 - d) Brief description of supply & installation
- The bid received without mention of above on the envelope shall not be accepted.
6. Bid received vide E-Mail/Fax/Telegram/Telex/Cable/bid in open condition will not be accepted.
 7. The company will not be responsible for any postal delay or non-receipt.
 8. **Validity:** The bid must be valid for 60 (Sixty) days from the date of opening of the bid.
 9. **Delivery:** The ordered materials shall have to be delivered, installed & commissioned at the specified locations as mentioned above within 15 (Fifteen) days from the date of receipt of the Work Order by Fax/Email etc.
 - 10 **EMD:** An amount of Rs. 2,300.00 (Rupees Two thousand Three hundred) only in form of Demand Draft/ Bank Guarantee in favour of Assam Gas Company Limited payable at Duliajan, Assam is also to be submitted along with the tender documents, without which the tenders will be outright rejected. The EMD of unsuccessful bidders shall be refunded after issue of Work Order to the successful bidders.
 11. **Payment :** 100% (Hundred Percent) payment shall be made to the supplier within 30 (thirty) days on receipt of technically correct bill in triplicate subject to complete supply & installation of materials and acceptance of all materials by Engineer In-charge of AGCL.
 12. Conditional bids are liable to rejection at the sole discretion of the Company.
 13. **Guarantee/Warrantee:** ACs and stabilizers should have a standard warranty of minimum twelve months and compressors should have a minimum warranty of sixty months from the date of installation.



14. **Applicability of Law & Jurisdiction:** The Order shall be governed and interpreted in accordance with the applicable laws of India and Dibrugarh Courts in the State of Assam shall have exclusive jurisdiction.

15. The Company reserves the right of rejecting any or all bids accepting any bid in part, without assigning any reason.

Thanking You,

Yours faithfully,



(G.K Sharma)
General Manager (I&TGG)

For MANAGING DIRECTOR



ANNEXURE I

TECHNICAL SPECIFICATION OF INVERTER SPLIT TYPE AIR CONDITIONER

Type: Split Type Dual Inverter AC,
Tonnage: 2.0 TON
Star rating: 3 Star
Refrigerant gas: R32
Compressor: Dual Rotary/ High EER Twin Rotary
Condensor Coil: Copper
ISEER Value: Minimum 3.5
Power Supply: 220-240Volts/ 50 Hz/ Single phase
Air flow volume: >1000CMH
Noise level (Indoor): Max 45 dB
Panel display: Yes
Auto Air Swing (Up and Down): Yes
Dual inverter: Yes
100% Copper: Yes
Remote with LCD display: Yes
Auto restart: Yes
Sleep Mode: Yes
Turbo mode: Yes
Timer: Yes
Self Diagnosis: Yes
Approved Brand: LG/VOLTAS/SAMSUNG/Bluestar/Lloyd/Carrier/ Hitachi/Daikin
Colour: White

TECHNICAL SPECIFICATION OF 5KVA STABILIZERS

- KVA Rating : 5KVA
- Application: Must be suitable for application for 2.0 Ton Inverter AC
- Working range of the Inverter AC (after connecting the stabilizer): 140-280 V
- Built in thermal overload protection
- Provision for wall mounting
- Fail safe circuit design
- Low & High Voltage cut off
- Initial Time Delay System
- Must have the provision of input voltage display
- **Approved Brand : V Guard, Microtek, Philips**



ANNEXURE II

TECHNICAL SPECIFICATION OF INVERTER SPLIT TYPE AIR CONDITIONER

Type: Split Type Dual Inverter AC,
Tonnage: 1.5 TON
Star rating: 3 Star
Refrigerant gas: R32
Compressor: Dual Rotary/ High EER Twin Rotary
Condensor Coil: Copper
ISEER Value: Minimum 3.5
Power Supply: 220-240Volts/ 50 Hz/ Single phase
Air flow volume: >900CMH
Noise level (Indoor): Max 40 dB
Panel display: Yes
Auto Air Swing (Up and Down): Yes
Dual inverter: Yes
100% Copper: Yes
Remote with LCD display: Yes
Auto restart: Yes
Sleep Mode: Yes
Turbo mode: Yes
Timer: Yes
Self Diagnosis: Yes
Approved Brand: LG/VOLTAS/SAMSUNG/Bluestar/Lloyd/Carrier/ Hitachi/Daikin
Colour: White

TECHNICAL SPECIFICATION OF 4 KVA STABILIZERS

- KVA Rating:4KVA
- Application: Must be suitable for application for 1.5 Ton Inverter AC
- Working range of the Inverter AC (after connecting the stabilizer): 140-280 V
- Built in thermal overload protection
- Provision for wall mounting
- Fail safe circuit design
- Low & High Voltage cut off
- Initial Time Delay System
- Must have the provision of input voltage display
- **Approved Brand : V Guard, Microtek, Philips**



ANNEXURE III

TECHNICAL SPECIFICATION OF 1.0 TON INVERTER SPLIT TYPE AIR CONDITIONER

Type: Split Type Dual Inverter AC,
Tonnage: 1.0 TON
Star rating: 3 Star
Refrigerant gas: R32
Compressor: Dual Rotary/ High EER Twin Rotary
Condensor Coil: Copper
ISEER Value: Minimum 3.5
Power Supply: 220-240Volts/ 50 Hz/ Single phase
Air flow volume: >850 CMH
Noise level (Indoor): Max 46 dB
Panel display: Yes
Auto Air Swing (Up and Down): Yes
Dual inverter: Yes
100% Copper: Yes
Remote with LCD display: Yes
Auto restart: Yes
Sleep Mode: Yes
Turbo mode: Yes
Timer: Yes
Self Diagnosis: Yes
Approved Brand: LG/VOLTAS/SAMSUNG/Bluestar/Lloyd/Carrier/ Hitachi/Daikin
Colour: White

